

48000 - Children's Hospital 3rd Floor Neuro Institute

06 March 2019 : 48000 - Children's Hospital 3rd Floor_Neuro Institute.est
Summary Report

No addendum noted

area	net	gross	base
CPT-1 MILLIKEN, CITY PROPER, EC1, RADIO ROW 153 (24"x24" - monolithic install) : 2' x 2' [split 38:full 121] [tileEdge= 472'11"]			140 >> 2' 62.22sy
area count=3	54.21sy	62.22sy	
CPT-2 MILLIKEN, CITY PROPER, UNDERGROUND, RADIO ROW 153 (24"x24" - monolithic install) : 2' x 2' [split 182:full 904] [tileEdge= 3407'5"]			995 >> 2' 442.22sy
area count=21	404.28sy	442.22sy	
CPT-3 MILLIKEN, CITY PROPER, EC1, ISLINGTON BOROUGH ECC229 (24"x24" - monolithic install) : 2' x 2' [split 38:full 153] [tileEdge= 587'1"]			172 >> 2' 76.44sy
area count=3	66.59sy	76.44sy	
LF-1 FORBO MARMOLEUM, LINEAR, WHITE CLIFFS 3575 (79" roll - flat laid) : width 6'7": cutTo13.00": seam 864'10" + 1024' = 1889 IF welding			[6'7"] x [1616'2"] gross
area count=83	1036.04sy	1182.21sy	
LF-2 FORBO MARMOLEUM, LINEAR, PEACOCK BLUE 5243 (79" roll - flat laid) : width 6'7": cutTo13.00": seam 12 lf welding			[6'7"] x [165'1"] gross
area count=32	90.07sy	120.73sy	
LF-3 FORBO MARMOLEUM, LINEAR, BLUE STROKE 5245 (79" roll - flat laid) : width 6'7": cutTo13.00": seam 7'10" + 25' = 33 lf welding			[6'7"] x [321'8"] gross
area count=50	161.15sy	235.25sy	
RB-1 4" JOHNSONITE RUBBER WALL BASE, BURNT UMBER 63 (straight @ carpet)			
area count=27	0.00sf	1328'4"	
RB-1 4" JOHNSONITE RUBBER WALL BASE, BURNT UMBER 63 (cove @ resilient/hard surfaces)			
area count=168	0.00sf	3924'6"	
TS-1 CARPET TO RESILIENT TRANSITION, TBD			
area count=15	0.00sf	66'11"	
TS-2 CARPET TO TERRAZZO TILE TRANSITION, TBD			
area count=11	0.00sf	71'10"	
TS-3 RESILIENT TO TERRAZZO TILE TRANSITION, TBD			
area count=2	0.00sf	12'	
Additional seam welding (match LF-1)			
area count=82	0.00sf	1023'5"	
Additional seam welding (match LF-2)			
area count=3	0.00sf	11'6"	
Additional seam welding (match LF-3)			
area count=4	0.00sf	24'5"	

Plan Total 1812.34sy

Exclude: terrazzo, ceramic tiles, concrete

* used 11.310 for forbo patterns, since finish plan had them rather mixed and not corresponding.

Note that I included base at terrazzo flooring (plans did not say if needs base or what type), so qualify.

No extra stock included

Order in full box amounts.

see next page for layout

48000 - Children's Hospital 3rd Floor Neuro Institute

06 March 2019 : 48000 - Children's Hospital 3rd Floor_Neuro Institute.est
Summary Report

Scale 1:410 (original drawing scale 1:131)

USED I1.3.10 FOR LOCATIONS OF LF-1 LF-2 LF-3



Hospital Los Angeles
We Treat Kids Better

FINISH LEGEND

PAINT SHEEN

FINISH LEGEND

11.3.21

FLOOR FINISH FLOOR SECTION A A01